

Your Touchstone Energy' Cooperative

Green CCR Landfill

Disposal of Coal Combustion Residuals (CCR) from Electric Utilities Final Rule CCR Landfill 2019 Annual Inspection Report

Big Rivers Electric Corporation 201 3rd Street Henderson, KY 42420

Project number: 60613512

January 10, 2020

Project number: 6058151512

Prepared for:

Big Rivers Electric Corporation 201 3rd Street Henderson, KY 42420

Prepared by:

Mark Keown, P.E. T: 502-656-3645

E: mark.keown@aecom.com

AECOM 500 West Jefferson Street Louisville, KY 40202 aecom.com



Copyright © 2020 by AECOM

All rights reserved. No part of this copyrighted work may be reproduced, distributed, or transmitted in any form or by any means without the prior written permission of AECOM.

Table of Contents

1.	Project Background	4
2.	Regulatory Requirements	4
3.	Review of Available Information	4
4.	Inspection Procedures & Observations	5
5.	Inspection Findings	6
CCR I	Landfill Geometry	6
CCR I	Landfill Volume	6
CCR I	Landfill Structural, Operational, and Safety Items	7
CCR I	Landfill Changes	7
6.	Recommendations – General Maintenance and Monitoring Conditions	7
	ll	
Active Areas		
Closed Areas		7

1. Project Background

Per United States Environmental Protection Agency (USEPA) Final Coal Combustion Residual (CCR) Rule §257.84 annual inspection by a qualified professional engineer is required for each CCR unit. At the request of Big Rivers Electric Corporation (BREC), AECOM completed the annual inspection in accordance with the CCR Rule requirements and prepared this annual Inspection report for the Green CCR Landfill at the Sebree Generating Station, located in Robards, Kentucky.

The CCR Rule requires a visual inspection by a licensed civil engineer of each CCR unit to ensure that the design, construction, operation and maintenance of the CCR unit is consistent with recognized and generally accepted good engineering standards. This inspection was performed in accordance with the scope of work presented in our proposal, dated August 23, 2019, executed under purchase order 255959 as part of general services agreement with Big Rivers Electric Corporation dated November 16, 2017.

2. Regulatory Requirements

The annual inspection criteria are specified in CCR Rule Section 257.84(b) (1) which at a minimum includes:

- (i) A review of available information regarding the status and condition of the CCR unit, including, but not limited to, files available in the operating record (e.g., the results of inspections by a qualified person, and results of the previous annual inspections); and
- (ii) A visual inspection of the CCR unit to identify signs of distress or malfunction of the CCR unit.

In addition to the annual inspections, 7-day inspection per CCR Rule Section 257.84 (a) are completed by BREC and are documented in the facility operating record.

Once the annual inspection has been completed, the CCR Rule Section 257.84(b) (2) requires the qualified professional engineer to prepare a report following each inspection that addresses the following:

- (i) Any changes in geometry of the structure since the previous annual inspection;
- (ii) The approximate volume of CCR contained in the unit at the time of the inspection;
- (iii) Any appearances of an actual or potential structural weakness of the CCR unit, in addition to any existing conditions that are disrupting or have the potential to disrupt the operation and safety of the CCR unit; and
- (iv) Any other change(s) which may have affected the stability of operation of the CCR unit since the previous annual inspection.

3. Review of Available Information

Prior to completing the visual inspection of the CCR unit, AECOM reviewed the 2018 Annual Inspection Report for the CCR unit, prepared by AECOM dated January 3, 2019. Any areas in need of repair were addressed by the report and BREC completed the appropriate repairs where necessary. The observations from the 2018 annual inspection completed by AECOM include:

On the east side of the landfill along the toe of the slope, ponded water was present; Water was present in the
drainage ditch along the haul road and BREC had recently reseeded the area of concern due to erosion;

Project number: 60581515

- Some surficial erosion/rills in cover material; particularly the northern side;
 - Minor to moderate erosion on active disposal areas and haul roads of the active area (working face);
- Seepage was present along the base of the expansion wall construction near the south end. The ground between the wall and drainage ditch was noted to be soft;
- Seepage present at the toe and lower slope of the east side of the landfill;

The 2018 inspection concluded "no deficiencies or disrupting conditions that would require immediate measures to remedy were identified in the inspection. The inspection findings consisted of maintenance items that were not observed to be signs or potential signs of significant structural weakness."

After the inspection observations were made available to BREC, corrective actions at the Green CCR Landfill were completed. The observations presented during the 2018 annual inspection were addressed in a timely manner by BREC. BREC has taken the following steps to rectify the previous inspections observations, the depressions on the slope has been repaired, and all other areas of minor erosion in the temporary cover will be addressed as the haul road and Mechanically Stabilized Poz-O-Tech (MSP) wall continue to develop.

These observations were repaired as soon as practical based on the mowing schedule and weather. Removing sediment buildup, filling low areas, and re-seeding activities were to be completed when such repair activities don't exacerbate any required maintenance.

In summary no deficiencies were identified, and the previously stated observations were addressed prior to submittal of this report.

4. Inspection Procedures & Observations

Per CCR Rule Section 257.84 (b) (3) the owner or operator of the CCR unit (BREC) must complete the initial inspection no later than January 18, 2016. This report summarizes the fifth annual inspection performed by BREC since the CCR Rule took effect April 17, 2015. The fourth inspection was completed on September 12, 2019. The inspection was completed by AECOM professional engineer Mark Keown, P.E. and AECOM staff engineer Scott Mesi. In addition to the annual inspection BREC completes 7-day inspections of the CCR unit in accordance with Section 257.84 of the CCR Rule.

The inspection consisted of visual assessment of the landfill and associated protective cover soil, vegetation, and storm water management structures. The inspection began on the west side along the MSP wall moving from north to south at the toe of the wall. The riprap check dams and erosion control matting were in good condition along the toe of the wall.

The inspection progressed to the south end of the landfill at the toe of the landfill moving to the east. This area appeared to be in good condition functioning as designed. Continuing to the east side of the landfill along the toe of the slope, there were no signs of flowing water or seepage and the area appeared to be stable.

After inspecting the toe of the south and east sides of the landfill, the inspection proceeded to the first bench on the east and south sides of the landfill working up to the top of the landfill. The vegetation, surface water controls, and protective cover within the area appear to typically be in good condition.

A lack of vegetation was observed at the northeast corner on the uphill slope of the top berm. Lack of vegetation was observed on the fifth berm from top on the west-southwest side. Lack of vegetation and slight erosion was observed in the northeast corner of the seventh berm from top. The lack of vegetation on this berm is likely due to mowing practices. Rutting and erosion was observed near the drain on the second berm from the top on the northeast side. As part of the regular Green CCR Landfill maintenance, BREC re-seeded this area of sparse vegetation during the fall when the weather conditions were conducive to vegetative growth.

Project number: 60581515

The north side of the landfill is active and appeared to be in good condition at the time of the inspection constructing the landfill as designed.

The inspection was limited to the portions of the landfill that had protective cover soils placed and were not part of the working face of the landfill. The working face of the landfill is maintained by BREC operations.

5. Inspection Findings

Per CCR Rule Section 257.84(b) (2) the following observations were made.

CCR Landfill Geometry

The Green CCR Landfill is used for the placement of coal combustion residual (CCR) material including primarily Poz-O-Tec and related materials. The landfill has a maximum elevation of approximately 606 feet above mean sea level (MSL), based on a topographic survey conducted by Associated Engineers in September 2019. The Green River lies to the east of the landfill and Groves Creek lies to the south of the landfill. The landfill has approximately 7 continuous benches on the south and east side, each higher in elevation until the top of landfill is reached. The north and west sides of the landfill are receiving CCR placement as part of BREC operations. An aerial photograph of the Green CCR Landfill is presented on the next page in Figure 1.



Figure 1: Big Rivers Green Landfill Overview

Changes to the landfill geometry since the previous 2018 annual inspection includes placement of additional CCR, protective cover soils and establishing vegetation on the landfill.

CCR Landfill Volume

The total volume of CCR material contained in the Green CCR Landfill was estimated to be 22.4 million cubic yards, based on a topographic survey conducted by Associated Engineers in September 2019.

Green CCR Landfill Big Rivers Electric Corporation

Project number: 60581515

CCR Landfill Structural, Operational, and Safety Items

No deficiencies or disrupting conditions that would require immediate measures to remedy were identified in the inspection. The inspection findings consisted of maintenance items that were not observed to be signs or potential signs of significant structural weakness.

BREC has been made aware of the aforementioned observations and are planning to repair as soon as practical. The observations were limited to sparse vegetation and erosion rills near the active face on the north side of the landfill.

CCR Landfill Changes

There have been no changes to the Green CCR Landfill since the previous 2018 annual inspection that may have the potential to affect the stability or operation of the CCR unit. Changes include typical operations activity such as, placement of additional CCR material and protective cover soil to meet the closure design grades of the landfill. The MSP wall is being constructed as designed and showed no signs of instability at the time of the inspection.

6. Recommendations — General Maintenance and Monitoring Conditions

Overall

- Continue regular mowing of all berms with vegetation control to prevent the growth of excessive woody plants and brushes.
- 2. Continue regular maintenance of minor erosion rills and rutting in timely manner.
- 3. Continue weekly inspection as required by the CCR mandated roles and submit Inspection Reports to the facility operating record in a timely manner.

Active Areas

1. Continue current maintenance practices.

Closed Areas

- 1. Continue current maintenance practices.
- 2. Continue to complete seasonal repairs such as reseeding in areas of sparse vegetation and filling in ruts caused by the tractor and mowing operations.
- 3. Continue to check catch basins for obstructions and clear as needed.